

**ADDENDUM NO. 2**  
**SAP 050-599-150**  
**Bridge No. 50K57**  
**Mower County, Minnesota**

**Letting Date: December 14, 2017 – 1:00 P.M.**

**Today's Date: December 13, 2017**

THIS ADDENDUM, CONSISTING OF ONE (1) PAGE ONLY SHALL BE CONSIDERED A PART OF THE ORIGINAL PROPOSAL FOR THE ABOVE REFERENCED PROJECT AND WILL BE BOUND WITH ALL SETS OF THE PROPOSAL SUBSEQUENTLY ISSUED.

**NOTICE TO BIDDERS:**

**Bidders shall take note of the note on the right side of *Section CC* on Sheet 3 which states:**

***“AGGREGATE BACKFILL (3149.2E COMPACTED IN 0.5’ LAYERS, INCIDENTAL TO CONSTRUCTION”.*** It is the intent of the Contract Documents that the backfill shall be classified as Common Borrow (sandy clay, pit run if it is convenient to the Contractor, etc.) which meets the gradation requirements of 3149.2E, in that no large or oversize material or organic material shall be used. This material shall be placed in 0.5’ lifts and thoroughly compacted. The furnishing, placement, and compaction of the material shall be considered incidental to the Bid Price for Common Borrow, and will not be paid for directly.

**If the excavated material is suitable for use as backfill, it shall be utilized in lieu of Common Borrow.**

**THE UNDERSIGNED ACKNOWLEDGES THE RECEIPT OF THIS ADDENDUM:**

---

**DATE:**

**END OF ADDENDUM**

**(Please confirm by email and/or fax as soon as possible – FAX: 507-437-7609)**