

ADDENDUM NO. 6 TO COMMON INTEREST COMMUNITY NUMBER 7, MOWER COUNTY, MINNESOTA

OAK PARK VILLAGE CONDOMINIUM
COMMON INTEREST COMMUNITY PLAT SITE PLAN

THIS COMMON INTEREST COMMUNITY PLAT HAS BEEN RECORDED AS PART OF THE DECLARATION FILED AS DOCUMENT NUMBER 204344 AND IN BOOK DEEDS, AT PAGE ON THE 21 DAY OF May, 2002 MOWER COUNTY RECORDER.

SURVEYOR'S CERTIFICATE

I, John H. Schulte IV, a duly Registered Land Surveyor under the state laws of Minnesota, on this 21 day of May, 2002, by these presents hereby certify that the plat of this Common Interest Community, located in Austin, Minnesota was prepared by me or under my direct supervision, and that the boundary thereof described as follows:

Lot 1, Block 1, Oak Park Village, as the same is platted and recorded in the office of the County Recorder of Mower County, Minnesota.

Together with Addendums Nos. 1, 2, 3, 4 and 5 to Common Interest Community Number 7, OAK PARK VILLAGE CONDOMINIUM, as the same are platted and recorded in the office of the County Recorder of Mower County, Minnesota.

ENGINEER'S CERTIFICATE

I, Steven J. Andersen, a Registered Professional Engineer for the State of Minnesota pursuant to Minnesota Statutes Section 515B.2-101(c), do hereby certify that with respect to Units Numbered 57, 58, 59 & 60, all structural components and mechanical systems of all buildings containing or comprising any units thereby created, but not necessarily the units, are substantially completed consistent with the plat for COMMON INTEREST COMMUNITY NUMBER 7, OAK PARK VILLAGE CONDOMINIUM.

Minnesota Registration No. 23152

Subscribed and sworn to before me this 21 day of May, 2002.



Elaine S. Wallace
Notary Public, Waseca County, Minnesota
My Commission Expires 1-31-2005

COUNTY SURVEYOR'S APPROVAL

Pursuant to Minnesota Statutes, Chapter 389.09 Subd. 2, this common interest community has been approved this 21 day of May, 2002.

Deputy Mower County Surveyor

COUNTY AUDITOR'S CERTIFICATE

Transfer entered this 29 day of May, 2002.

County Auditor
Mower County, Minnesota

NOTES

- L. C. E. DENOTES LIMITED COMMON ELEMENT.
- SEE SHEET 2 FOR UTILITY EASEMENTS AND THEIR RELATION TO BUILDINGS.
- SEE SHEET 3 FOR EXTERIOR DIMENSIONS OF FOUNDATION WALLS.
- SEE SHEET 3 FOR FLOOR PLANS OF UNITS 57, 58, 59 & 60.
- UNITS NUMBERED 1 THROUGH 48, 69 THROUGH 72, AND 77 THROUGH 80 ARE EXISTING CONDOMINIUM UNITS.

BASIS OF BEARING SYSTEM :

ALL BEARINGS ARE BASED UPON THE BEARING OF THE NORTH LINE OF THE NW1/4 SECTION 34-T103N-R18W, WHICH IS ASSUMED TO BE SOUTH 89°15'40" WEST.

ADDENDUM NO. 6

And together with all that part of Lot 2, Block 1, Oak Park Village, as the same is platted and recorded in the office of the County Recorder of Mower County, Minnesota; described as follows:

Commencing at the southeasterly-most corner of said Lot 2, Block 1, Oak Park Village; thence North 00°35'30" West a distance of 352.07 feet, along the easterly line of said Lot 2, and a northerly extension thereof; thence North 59°46'06" West a distance of 157.40 feet, to a point on the centerline of a 64 foot wide utility easement, as shown on the plat of said Oak Park Village; thence Northeasterly along the centerline of said northerly-southerly platted utility easement, as follows: North 27°44'49" East a distance of 79.93 feet; Northeasterly a distance of 96.86 feet, on a tangential curve, concave to the northwest with a radius of 200.00 feet and a central angle of 27°44'49"; North 00°00'00" East a distance of 71.40 feet, on a tangential line; Northerly a distance of 51.41 feet, on a tangential curve, concave to the west with a radius of 200.00 feet and a central angle of 14°43'40", to the point of beginning;

thence Northerly a distance of 43.70 feet, on a continuation of the last described curve, with a radius of 200.00 feet, a central angle of 12°31'10", and a chord bearing of North 20°59'15" West;

thence North 27°14'50" West a distance of 68.68 feet, on a tangential line;

thence Northwesterly a distance of 25.06 feet, on a tangential curve, concave to the southwest, with a radius of 288.08 feet and a central angle of 04°59'06";

thence North 32°13'56" West a distance of 31.73 feet, on a tangential line;

thence South 61°03'03" West a distance of 159.36 feet, to a point of deflection on the westerly line of said Lot 2;


thence South 18°24'36" East a distance of 136.11 feet, on a westerly line of said Lot 2, to the westerly-most corner of the south tract as described in Addendum No. 5 to Common Interest Community Number 7, Mower County, Minnesota, Oak Park Village Condominium;

thence North 72°04'49" East a distance of 181.70 feet, on the northerly line of said south tract as described in said Addendum No. 5, to the point of beginning.

Constitutes Common Interest Community Number 7, OAK PARK VILLAGE CONDOMINIUM. The common interest community plat consists of eight pages and 6 addendums, and fully and accurately depicts all of the information required by Minnesota Statutes Section 515B.2-110.


John H. Schulte IV, Registered Land Surveyor
Minnesota Reg. No. 13807

Subscribed and sworn to before me this 21 day of May, 2002.



Elaine S. Wallace
Notary Public, Waseca County, Minnesota
My Commission Expires 1-31-2005

LOCATION MAP



LEGEND

- = 5/8" Diameter x 16" iron monument (capped RLS 13807) - Placed
- = Iron stake monument - Found
- P.O.B. = Point of beginning of description



SCALE IN FEET




Table with 3 columns: LINE/CURVE, BEARING, DISTANCE. Includes LINE A, LINE B, LINE C, CURVE D, CURVE E.


SOUTH LINE N1/2 NW1/4 SEC. 34-T103N-R18W

BLOCK 1 OAKWOOD WEST SECOND SUBDIVISION
BENCHMARK TOP OF NUT OF FIRE HYDRANT AT NORTHEAST CORNER OF MOOSE LODGE ELEVATION = 1225.95 NGVD
BLOCK 3 OAKWOOD WEST SUBD.

JONES, HAUGH & SMITH INC
CONSULTING ENGINEERS & LAND SURVEYORS
515 SOUTH WASHINGTON AVENUE
ALBERT LEA, MINNESOTA 56007
MAY 2002
DRAWN BY GENE BUHR

ADDENDUM NO. 6 TO COMMON INTEREST COMMUNITY NUMBER 7, MOWER COUNTY, MINNESOTA

OAK PARK VILLAGE CONDOMINIUM
SITE PLAN DETAILS



DESCRIPTION OF ADDITIONAL REAL ESTATE

Lots 2 and 3, Block 1, Oak Park Village, as the same is platted and recorded in the office of the County Recorder of Mower County, Minnesota.

Less Addendums Nos. 2, 3, 4 and 5 to Common Interest Community Number 7, OAK PARK VILLAGE CONDOMINIUM, as the same are platted and recorded in the office of the County Recorder of Mower County, Minnesota.

ADDENDUM NO. 6

And less all that part of Lot 2, Block 1, Oak Park Village, as the same is platted and recorded in the office of the County Recorder of Mower County, Minnesota; described as follows:

Commencing at the southeasterly-most corner of said Lot 2, Block 1, Oak Park Village; thence North 00°35'30" West a distance of 352.07 feet, along the easterly line of said Lot 2, and a northerly extension thereof; thence North 59°46'06" West a distance of 157.40 feet, to a point on the centerline of a 64 foot wide utility easement, as shown on the plat of said Oak Park Village; thence Northeasterly along the centerline of said northerly-southerly platted utility easement, as follows: North 27°44'49" East a distance of 79.93 feet; Northeasterly a distance of 96.86 feet, on a tangential curve, concave to the northwest with a radius of 200.00 feet and a central angle of 27°44'49"; North 00°00'00" East a distance of 71.40 feet, on a tangential line; Northerly a distance of 51.41 feet, on a tangential curve, concave to the west with a radius of 200.00 feet and a central angle of 14°43'40", to the point of beginning;

thence Northerly a distance of 43.70 feet, on a continuation of the last described curve, with a radius of 200.00 feet, a central angle of 12°31'10", and a chord bearing of North 20°59'15" West;

thence North 27°14'50" West a distance of 68.68 feet, on a tangential line;

thence Northwesterly a distance of 25.06 feet, on a tangential curve, concave to the southwest, with a radius of 288.08 feet and a central angle of 04°59'06";

thence North 32°13'56" West a distance of 31.73 feet, on a tangential line;


thence South 61°03'03" West a distance of 159.36 feet, to a point of deflection on the westerly line of said Lot 2;

thence South 18°24'36" East a distance of 136.11 feet, on a westerly line of said Lot 2, to the westerly-most corner of the south tract as described in Addendum No. 5 to Common Interest Community Number 7, Mower County, Minnesota, Oak Park Village Condominium;

thence North 72°04'49" East a distance of 181.70 feet, on the northerly line of said south tract as described in said Addendum No. 5, to the point of beginning.

LINE/CURVE	BEARING	DISTANCE
LINE A	S 23°04'42" W	34.71'
LINE B	N 60°57'14" W	38.29'
LINE C	N 38°32'05" W	67.60'
CURVE D	CB N 44°08'45" W	
CURVE E	CA 12°31'10" 43.70'	
	CB N 20°59'15" W	

LOCATION MAP



LEGEND

- = 5/8" Diameter x 16" iron stake monument (capped RLS 13807) - Placed
- = Iron stake monument - Found
- Ⓢ = Utility Easement

NOTE:
THE LOCATION AND DIMENSIONS OF THE ROADWAY, UTILITY AND DRAINAGE EASEMENTS ARE SET FORTH IN THAT DOCUMENT RECORDED IMMEDIATELY PRIOR HERETO. THE EASEMENTS CONTAINED THEREIN BOTH BENEFIT AND BURDEN OAK PARK VILLAGE CONDOMINIUM.

BLOCK 1
OAKWOOD WEST SECOND SUBDIVISION


BLOCK 3
OAKWOOD WEST SUBD.

JONES, HAUGH & SMITH INC
CONSULTING ENGINEERS & LAND SURVEYORS
515 SOUTH WASHINGTON AVENUE
ALBERT LEA, MINNESOTA 56007
MAY 2002
DRAWN BY GENE BUHR

ADDENDUM NO. 6 TO COMMON INTEREST COMMUNITY NUMBER 7, MOWER COUNTY, MINNESOTA

OAK PARK VILLAGE CONDOMINIUM


SITE PLAN DETAILS AND FLOOR PLAN



BUILDING 15

UNITS 57, 58, 59 & 60

EXTERIOR DIMENSIONS OF FOUNDATION WALLS



BUILDING 15

UNITS 57, 58, 59 & 60

FLOOR PLAN

ALL 4 GARAGES
CEILING ELEV = 1230.30
FLOOR ELEV = 1222.30



NOTES TO FLOOR PLAN:

EXTERIOR UNIT BOUNDARY WALLS (EXCEPT AT GARAGES) ARE TYPICALLY 0.55 FEET IN THICKNESS.

INTERIOR UNIT BOUNDARY DIVIDING WALLS ARE TYPICALLY 0.86 FEET IN THICKNESS.

EXTERIOR WALLS AT GARAGES ARE TYPICALLY 0.33 FEET IN THICKNESS.

INTERIOR UNIT BOUNDARY DIMENSIONS SHOWN ARE TO THE INSIDE FACE OF SHEETROCK WALLS.

FLOOR AND CEILING ELEVATIONS ARE REFERENCED TO THE BENCHMARK ELEVATION SHOWN ON SHEET 1.

JONES, HAUGH & SMITH INC
CONSULTING ENGINEERS & LAND SURVEYORS
515 SOUTH WASHINGTON AVENUE
ALBERT LEA, MINNESOTA 56007

MAY 2002
DRAWN BY GENE BUHR